BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/03/2014-15, Date:31.10.2014.

ITEM NO: 53

SCHEDULE-B

NAME OF WORK: Ward Maintanance for Gangmens, Tractors & JCB for Removing silt & debries in the drains road side burms in Dasarahalli ward No 15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **N SHIVANANDA**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	6946.8	65.0	Rupees Sixty Five Only
2	Clearing and grubbing road land including uprooting rank vegetating, grass, bushes, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials with a lead of 100 metres from road boundary, labour charge Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	21833	5.0	Rupees Five Only
3	Providing JCB to Ward maintenance Complete as per specification and direction of Engineer-in-charge of the work.	Days	45	6000.0	Rupees Six Thousand Only
4	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	6946.8	63.91	Rupees Sixty Three and Ninety One Paise Only

N Shivananda

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

N Shivananda

Signature of the Contractor

Executive Engineer